NO: AM1(10)83/4320

dt.21.3.90

CIRCULAR No. 289

Sub; - Gap between W.C. van outlet & tran.

It has been observed with commern that the gap between W.C. pan outlet & trap is not filled properly as per specification, with the result that seepage occurs in the toilets, which is visible on the walls also. The seepage from the W.C. can be avaided if the joint between W.C. pan and trap is filled properly and in time as per specification.

All the field staff are therefore, directed to sheck this joint properly to avoid chances of leakage. In this context the Assistant Engineer incharge of the work shall perform 50% test check and Executive Engineer shall check as many as possible No flooring should be laid till this joint is checked properly. These instructions should be brought to the notice of all the field staff up to the level of J.E.

(V.S. Marti)
Engineer Nember

Copy tos-

1. All Zonal Chief Enginee-r with 25 spare copies for circulation.

- 2. C.E.(Q.C.) with 10 spare copies.
- 3. G.M., I.S.B.T. with 5 spare copies.
- 4. All E.Os & A.Es E.M. office.
- 5. C.E. (Special project cell).

7-11 mm/113